

20' GRACO GH2 SPRAY FOAM TRAILER RIG



Rig Address:

8303 Audubon Road, Chanhassen, MN 55317, USA

952.279.6400

| Qty | Item / Product | Description |
|-----|------------------------|---|
| 1 | GH-2 Reactor Package | SYSTEM,GH-2,10KW,3PH,PC, 250' HOSE & WHIP |
| 1 | PC Fusion Gun 02 | GUN, FUSION PC, ROUND 02 |
| 2 | T3 Pumps | PUMP, TRANSFER, 3:1, T3, Carbon Steel |
| 1 | Trailer | 8.5 x 20V: Tag Along 14,000# GVWR - (1) Side Door - (2) Barn Doors - ATP Rock Guard -LED Lights -Electric Brakes -Spare Tire |
| 1 | Interior Package Build | <p>IDI NON SLIDER SERIES INTERIOR PAK - Combo Unit</p> <p>Extra Trailer Details:</p> <p>Tires - 235/80/R16 Load Range E</p> <p>Trailer Jack - 7,000 lb. Lift Jack</p> <p>Trailer Sides - Paneling Taped and Screwed</p> <p>Doors - Barn Doors have bar locks and Side Doors have flush lock with bar lock. Leaf Springs. Electric drum brakes</p> <p>Equipment: 50kw Generator with Fuel Tank (1ph or 3ph) (260681 or 239500) or 40 kw option 239498</p> <p>7.5 HP Electric Compressor with 60 Gallon Fuel Tank (221620 or 146563)</p> <p>Tsunami Pure-10 Dryer (239955)</p> <p>Allegro Double Worker Ambient Pump w/ 21400' Hose & (2) Full Face Masks (146571)</p> <p>Dometic Rooftop Brisk AC w/ Interior Trim (237529)</p> <p>Recessed Electric Wall Heater (221581)</p> <p>Underbelly Foam Insulation (146629)</p> <p>Interior Pak: Closed Cell Insulated Walls & Ceiling, Rubber Diamond Plate Floors, Gloss White Plywood Walls, White Ceiling, Trim Out, Barrel Bracing with Fluid Tube Set, Work Bench w/ Vise Mounted), Spray Hose Rack, Fresh Air Hose Rack ProPak Plumbing & Electrical.</p> <p>IDI Tool and Safety Kit with IDI Sign Package: (1) SDS Book (1) Non-Sparking Bung Wrench, (1) 12 Pack Nitrile Dipped Gloves, (1) 25 Pack Hood & Boot Suits, (2) Half Mask Respirators w/ Cartridges, (1) Eye Wash Station, (1) Fire Extinguisher, (1) First Aid Kit,(1) Desiccant Dryer</p> |