Date: 11/18/2024

20’ GRACO R2 E30 NON ELITE SPRAY FOAM TRAILER RIG

Rig Address:
1125 Avenue R, Grand Prairie, TX 75050
952.279.6400

Contact: **Phone#:** **Email:**
IDI Rep: **Rig Team Member:**

Qty	Item / Product	Description
1	GRACO R2 E30 Non Elite Proportioner	PROPORTIONER, E-30, 15KW, R2
1	Whip	HOSE, WHIP, 1/4ID, 2000PSI, 10FT
5	Spray Hoses	HOSE, HTD, 2000, 3/8, W/RTD AND SG
1	Carlisle ST1 Gun 02	GUN D MC 02 MT W ACCY KIT
2	T3 Pumps	PUMP, TRANSFER, 3:1, T3, Carbon Steel
1	Trailer	8.5 x 20V: Tag Along 14,000# GVWR - (1) Side Door - (2) Barn Doors - ATP Rock Guard -LED Lights -Electric Brakes - Spare Tire
1	Interior Build Package	Extra Trailer Details: Tires - 235/80/R16 Load Range E Trailer Jack - 7,000 lb. Lift Jack Trailer Sides - Paneling Taped and Screwed Doors - Barn Doors have bar locks and Side Doors have flush lock with bar lock. Leaf Springs. Electric drum brakes Equipment: 45kw Generator with Fuel Tank (3ph) 7.5 HP Electric Compressor with 60 Gallon Fuel Tank Tsunami Pure-10 Dryer Allegro Double Worker Ambient Pump w/ 21400' Hose & (2) Full Face Masks Dometic Rooftop Brisk AC w/ Interior Trim Recessed Electric Wall Heater Underbelly Foam Insulation Interior Pak: Closed Cell Insulated Walls & Ceiling, Rubber Diamond Plate Floors, Gloss White Plywood Walls, White Ceiling, Trim Out, Barrel Bracing with Fluid Tube Set, Work Bench w/ Vise Mounted), Spray Hose Rack, Fresh Air Hose Rack ProPak Plumbing & Electrical. IDI Tool and Safety Kit with IDI Sign Package: (1) SDS Book (1) Non-Sparking Bung Wrench, (1) 12 Pack Nitrile Dipped Gloves, (1) 25 Pack Hood & Boot Suits, (2) Half Mask Respirators w/ Cartridges, (1) Eye Wash Station, (1) Fire Extinguisher, (1) First Aid Kit,(1) Desiccant Dryer

IDI-INSULATION.COM

Pricing and lead times are subject to change based on market conditions and availability. This quotation does not include tax or shipping costs. These will be added accordingly at the time of sale.

Contact us to Explore Available Options at
952.279.6400